

ADDENDA

GENERAL

1.01 The following sets forth the format for issued Addenda.

ADDENDUM NO. 01, dated September 21, 2026.

RE: ADA UPGRADES AND RAISED WALKWAY REMOVAL
OWNER PROJECT NO.: 10372448 & 10371729 / 233263 & 233755
AT
EVANS COMMUNITY ADULT SCHOOL
located at 717 N. Figueroa Street, Los Angeles, CA 90012

FROM: OWNER: LOS ANGELES UNIFIED SCHOOL DISTRICT
FACILITIES CONSTRUCTION CONTRACTS
333 S. Beaudry Ave., 28th Fl.
Los Angeles, CA 90017

TO: ALL PROSPECTIVE BIDDERS:

This Addendum forms a part of the Contract Documents and modifies the Bidding Documents dated September, 2026, as noted below. Acknowledge receipt of the Addendum in the space provided on Document 00 4100 - Bid and Acceptance Form. Failure to do so may result in the bid being deemed non-responsive.

The Addendum consists of **26** pages and **8** drawings.

A. CHANGES TO BIDDING DOCUMENTS

1. Remove section 00 0110 Table of Contents (5 pages) and replace with revised 00 0110 Table of Contents, issued with this addendum (5 pages).

B. CHANGES TO SPECIFICATIONS:

2. Remove section 01 5000 Construction Facilities and Temporary Controls (18 pages) and replace with revised section 01 5000 Construction Facilities and Temporary Controls issued with this addendum (19 pages).

C. CHANGES TO DRAWINGS:

1. Remove first cover page with bid no. 2610011.
2. Remove structural drawings (pages S-0.1 thru S-4.1) and replace with revised structural drawings (pages S-0.1 thru S-4.1) issued with this addendum.

D. OTHER CHANGES AS SET FORTH: N/A

ADDENDUM NO. 01

ADA UPGRADES & RAISED WALKWAY REMOVAL
EVANS COMMUNITY ADULT SCHOOL

REVISED 7/11/2018
ADDENDA
00 9113-1

- E. Clarification or any other notice of a change in the Bidding Documents will be issued only by the OWNER office of Facilities Construction Contracts and only in the form of a written Addendum, transmitted by fax or e-mail to all who are known by the issuing office to have received a complete set of Bidding Documents. Any other purported Addenda are void and unenforceable.

END OF ADDENDUM NO. 01

TABLE OF CONTENTS

DIVISION 00 - PROCUREMENT AND CONTRACTING REQUIREMENTS		Number of Pages
00 0101	Project Title Page	01
00 0110	Table of Contents	05
00 1116	Invitation to Bid	04
00 2113	Instructions to Bidders	08
	Procurement Job Aid	09
00 2513	Pre-Bid Meeting (Mandatory)	01
00 3000	Available Information	02
00 3126	OWNER’S List of Pre-qualified Asbestos Abatement Subcontractors	01
00 3148	Project Directory	04
00 4001	Required Bid Forms	01
00 4100	Bid and Acceptance Form	05
	Addendum of Provisions Required of Federally Funded Contracts - FEMA Awards	15
	Internal Revenue Code Section 179D Allocation Statement	01
	Sample 179D Assumptions and Calculations	01
00 4313	Bid Security Form	01
00 4336	Subletting and Subcontracting Fair Practices Act List	01
00 4340	Disabled Veteran Business Enterprises (DVBE) School Facilities Program	01
00 4500	Certification Requirements	05
	Exhibit A - LAUSD Board Resolution Questions	01
00 4519	Non-Collusion Affidavit	01
00 6113	Payment Bond (Labor and Material)	01
00 6114	Performance Bond.	03
00 6217	Certificate of Insurance for Hazardous Materials	01
00 7000	General Conditions	97
00 7300	Supplementary Conditions	05
00 7316	Owner Controlled Insurance Program (OCIP)	195
00 7339	Small Business Enterprise (SBE) School Facilities Program	01
00 7349	Project Stabilization Agreement (PSA)	63
00 9110	Pre-Bid Clarification	01
00 9113	Addendum No. 1	07
DIVISION 01 - GENERAL REQUIREMENTS – DESIGN BID BUILD		
01 1100	Summary of the Work	03
01 1216	Phasing of the Work	03

ADDENDUM NO. 1

ADA UPGRADES & RAISED WALKWAY REMOVAL
 EVANS COMMUNITY ADULT SCHOOL
 BEST VALUE

08/11/2026
 TABLE OF CONTENTS
 00 0110-1

01 1219	Phasing of the Work Appendix A	03
01 2513	Product Procedures for Substitutions “or Equal”	03
01 2613	Request for Clarification	02
01 2973	Schedule of Values	03
01 2976	Progress Payment Procedures	06
01 3113	Project Coordination.....	04
01 3119	Project Meetings	07
01 3129	Partnering.....	02
01 3216	Construction Schedule for Small Projects	11
01 3229	Project Forms	06
	Forms.....	01
01 3300	Submittal Procedures	08
01 4213	Abbreviations, Symbols and Acronyms	12
01 4523	Testing and Inspection.....	11
01 4524	Environmental Import/Export Material Testing	16
01 5000	Construction Facilities and Temporary Controls.....	19
01 5719	CEQA Mitigations	06
01 6000	Product Requirements	06
01 7329	Cutting and Patching.....	07
01 7418	Water Pollution Control.....	04
01 7419	Construction & Demolition Waste Management.....	04
01 7700	Contract Closeout	07
01 7836	Warranties	03
01 7900	Maintenance & Operations Staff Demonstration and Training.....	09
01 9113	General Commissioning Requirements	14

DIVISION 02 - EXISTING CONDITIONS

02 2600	Abatement of Hazardous Materials.....	04
02 4116	Demolition	04
02 8213	Asbestos Abatement & Asbestos Related Disturbance	30
	Approval for Request to Advertise.....	01
	Phase I – Asbestos Engineering Assessment	99
	Phase II – Attachment A, Project Manual for Asbestos Removal	15
02 8216	Asbestos Abatement of Non-Friable Floor Tile	15
02 8223	Removal of Asbestos Containing Asphalt	10
02 8333	Lead Abatement and Lead Related Construction Work.....	85

ADDENDUM NO. 1

ADA UPGRADES & RAISED WALKWAY REMOVAL
EVANS COMMUNITY ADULT SCHOOL
BEST VALUE

08/11/2026
TABLE OF CONTENTS
00 0110-2

DIVISION 03 - CONCRETE

03 0130 Restoration and Cleaning of Concrete 04

03 1000 Concrete Forming Accessories..... 08

03 2000 Concrete Reinforcing..... 07

03 3000 Cast-In-Place Concrete 28

DIVISION 05 - METALS

05 0513 Hot-Dip Galvanizing 06

05 1200 Structural Steel Framing..... 17

05 4000 Cold Rolled Metal Framing..... 11

05 5000 Metal Fabrications 09

DIVISION 06 - WOOD, PLASTICS, AND COMPOSITES

06 1000 Rough Carpentry..... 11

06 1643 Gypsum Sheathing..... 05

06 2000 Finish Carpentry 04

DIVISION 07 - THERMAL AND MOISTURE PROTECTION

07 2100 Thermal Insulation..... 07

07 2500 Gypsum Board Weather Resistant Barrier and Air Barrier System..... 04

07 2600 Vapor Barriers..... 04

07 6000 Flashing and Sheet Metal 06

07 8413 Penetration Firestopping 12

07 9200 Joint Sealants 07

DIVISION 08 - OPENINGS

08 1113 Hollow Metal Doors and Frames 13

08 3116 Access Panels and Frames..... 03

08 4113 Aluminum Entrances and Storefronts 12

08 7100 Door Hardware 34

08 8716 Anti-Graffiti and Impact Control Films 05

DIVISION 09 - FINISHES

09 0561 Moisture Testing for Flooring Installation..... 06

09 2216 Non-Structural Metal Framing 11

09 2423 Cement Plaster and Metal Lath 16

09 2900 Gypsum Board 12

09 3013 Ceramic Tiling 12

09 5113 Acoustical Panel Ceilings..... 10

ADDENDUM NO. 1

ADA UPGRADES & RAISED WALKWAY REMOVAL
EVANS COMMUNITY ADULT SCHOOL
BEST VALUE

09 6513	Rubber Base	04
09 6523	Luxury Vinyl Tile	06
09 8100	Acoustical Insulation	03
09 9000	Painting and Coating.....	10
09 9013	Painting of Existing Facilities	26
09 9623	Graffiti-Resistant Coatings	04

DIVISION 10 - SPECIALTIES

10 1400	Signage.....	16
10 2113	Phenolic Toilet Compartments.....	10
10 2813	Toilet Accessories.....	06
10 2815	Hand and Hair Dryers.....	08
10 4413	Fire Extinguishers and Cabinets.....	05

DIVISION 22 – PLUMBING

22 0500	Common Work Results for Plumbing.....	10
22 0513	Basic Plumbing Materials and Methods	32
22 0553	Plumbing Identification	05
22 0700	Plumbing Insulation.....	09
22 1000	Plumbing	21

DIVISION 23 - HEATING, VENTILATING, AND AIR CONDITIONING

23 0513	Basic HVAC Materials and Methods.....	21
23 2013	Above Ground HVAC Piping	15
23 8000	Heating, Ventilating and Air Conditioning Equipment.....	26

DIVISION 26 - ELECTRICAL

26 0500	Common Work Results for Electrical.....	07
26 0513	Basic Electrical Materials and Methods.....	18
26 0516	Medium-Voltage Cables, Splices and Terminations	06
26 0519	Electrical Power Conductors and Cables	08
26 0526	Grounding and Bonding	05
26 0533	Raceways and Boxes Fitting and Supports.....	15

DIVISION 28 – ELECTRONIC SAFETY AND SECURITY

28 1000	Access Control System (ACS)	28
28 3100	Fire Detection and Alarm	42

DIVISION 31 – EARTHWORK

31 1000	Site Clearing.....	02
---------	--------------------	----

ADDENDUM NO. 1

ADA UPGRADES & RAISED WALKWAY REMOVAL
EVANS COMMUNITY ADULT SCHOOL
BEST VALUE

08/11/2026
TABLE OF CONTENTS
00 0110-4

31 2200 Grading..... 03

31 2319 Excavation and Fill for Structures..... 07

31 2326 Base Course 03

DIVISION 32 – EXTERIOR IMPROVEMENTS

32 0117 Pavement Repair..... 04

32 0190 Operation and Maintenance of Planting..... 07

32 1216 Asphalt Paving..... 05

32 1236 Seal for Bituminous Surfacing 03

32 1313 Site Concrete Work..... 10

32 1713 Precast Concrete Parking Bumpers..... 02

32 1723 Pavement Markings 03

32 1726 Detectable Warning Surfacing 08

32 3113 Chain Link Fences and Gates..... 13

32 3119 Ornamental Fences and Gates 07

32 8413 Potable Water Irrigation 20

32 8416 Irrigation Controls..... 06

32 9000 Planting 19

32 9113 Lawns and Grasses 13

END OF TABLE OF CONTENTS

SECTION 01 5000

CONSTRUCTION FACILITIES AND TEMPORARY CONTROLS

PART 1 - GENERAL

1.01 SECTION INCLUDES

- A. Temporary utilities, construction facilities and temporary controls to be provided, maintained, relocated, and removed by CONTRACTOR.
- B. Temporary office furnishings and office equipment.
- C. Project signage.

1.02 QUALITY ASSURANCE

- A. CONTRACTOR shall comply with applicable laws and regulations of authorities having jurisdiction including, but not limited to, the following:
 - 1. Building Code requirements.
 - 2. Division of the State Architect.
 - 3. Health and safety regulations.
 - 4. Utility company regulations.
 - 5. Police, fire department and rescue squad requirements.
 - 6. Environmental protection regulations.
- B. CONTRACTOR shall arrange for the inspection and testing of each temporary utility prior to use. Obtain required certifications and permits and transmit to OAR.
- C. CONTRACTOR provided facilities are to be in place and available for OWNER use and occupancy within 45 calendar days following the date of issue of the Notice to Proceed and shall remain in place and available for OWNER use and occupancy throughout the full term of the Contract.

1.03 SUBMITTALS

- A. Temporary Utilities: Submit to OAR reports of tests, inspections, meter readings, certifications, permits and similar procedures performed on temporary utilities.

B. Project Signage / Banner: Submit to OAR for review and approval.

1. Shop Drawings: Elevation showing the text, OWNER sign and color of project signage, jointing, fittings and location of grommets.
2. Certification: Submit certification attesting fabric is certified as flame retardant, in accordance to NFPA 701, Standard Methods of Fire Tests for Flame Propagation of Textiles and Films.

1.04 PROJECT IDENTIFICATION SIGNAGE AND BANNERS

A. Provide the following project identification information:

1. “Your School Bond Funds at Work”.
2. “Safe and Updated”.
3. “Construction Anticipated to Start in 2026”.
4. \$1,037,569 Million Investment.
5. “Creates an Estimated 25 Jobs.
6. OWNER: ‘Los Angeles Unified School District’
7. Name of School: Evans Community Adult School
8. Name of Project: ADA Upgrades & Bridge Removal
9. Name of LAUSD School Superintendent: Andres E. Chait (acting)
10. Name of LAUSD BOE Members: Tanya Ortiz Franklin, Kelly Gonez, Karla Griego, Nick Melvoin, Sherlett Hendy Newbill, Rocio Rivas, Scott Scmerelson.
11. Name of the Architect and Engineers: Architects McDonald, Soutar & Paz, Inc.; Breen Design Group (Civil & MEP); Coffman Engineers; JDC Landscape Architect
12. **Name of the CONTRACTOR: {INSERT NAME OF CONTRACTOR}.**
13. Name of the Board District: Board District 2

B. Project Sign:

1. CONTRACTOR shall furnish and install 1 Project Sign on the Project site at a location established by OAR. For graphical layout refer to Appendix A. OAR will provide the information to be posted on the sign. A draft of

the proposed sign shall be submitted to OAR for review and approval before fabrication.

2. Sign shall be direct printed on an aluminum sheet 0.08 thick, adhered to a 3/4 inch thick exterior grade plywood. Electronic file of graphic shall have a minimum resolution of 150 dpi at two feet by four feet. Provide posts, bracing and perimeter framing with intermediate backing not to exceed two feet on center. Size: eight feet wide by four feet high. Size of building rendering shall be approximately six feet wide by three feet high.
- C. No other signs shall be displayed without approval of OAR. At CONTRACTOR'S expense and without limitation remove and/or relocate Project signage and related facilities as rapidly as required in order to provide for progress of the Work.
- D. CONTRACTOR shall remove Project Identification Signage at Substantial Completion of the Work.

1.05 TEMPORARY UTILITIES (N/A)

1. Provide temporary phone, data service and distribution to Project site
- A. and appurtenances.

1.06 TEMPORARY OFFICES

- A. CONTRACTOR shall provide Project Site temporary office facilities for his own use, and in addition shall provide and maintain a minimum of one **8' X 40'** construction trailer on the Project site for use by OWNER for the duration of the Work. Construction trailer shall be accessible by OWNER and/or INSPECTOR on a 7 day a week 24-hour basis. CONTRACTOR shall provide the necessary materials and labor to provide the trailer with access for disabled persons on request by the OAR. Trailer shall include, at a minimum, the following:
 1. Conference room with a table and adequate seating for twelve.
 2. One bathroom.
 3. An open work area with devising partitions as required by OWNER.
 4. Two enclosed, separate offices with windows and lockable doors.
- B. Trailer shall be furnished with two exterior entrance doors with one located in a separate office. Each door shall be furnished with 'Smart Key' technology on both the dead bolt and cylinder lock. Provide six keys for each locking device. Exterior doors and windows shall be provided with exterior mounted burglar bars. Windows shall be provided with operable window shades. Security of trailer and

contents is a continuous obligation of CONTRACTOR and shall be equipped with local sounding security system.

- C. Trailer shall have ample headroom, 8-foot minimum, and shall be lighted, heated, ventilated, and air-conditioned. Provide an electrically chilled bottled water fountain of 5-gallon capacity. Purified water shall be supplied in 5-gallon containers, delivered weekly, with four spares on hand after each re-supply visit. As an option, CONTRACTOR may maintain a minimum of two 24 500ml bottles cases of purified water in owner trailer throughout the duration of the project.
- D. The separate offices shall each be approximately 120 square feet in size and shall be furnished with a minimum of four 120 volt single phase convenience outlets with one 4' long multi-outlet power strip (such as Legrand Model #PM48C) at each outlet location as well as one telephone jack and one data/LAN outlet. The conference room shall be approximately 200 square feet in size and shall be furnished with a minimum of eight 120 Volt single phase convenience outlets with one telephone jack and one data/LAN outlet.
- E. CONTRACTOR shall coordinate floor plan and location of electrical, telephone, data outlets with OAR prior to ordering and delivering the trailer.
- F. At CONTRACTOR'S expense and without limitation remove and/or relocate temporary office(s) and related facilities as rapidly as required in order to provide for progress of the Work.
- G. CONTRACTOR shall remove waste bin trash from OAR'S trailer, vacuum OAR'S trailer floors and/or mop OAR'S trailer floors once per week. Provide trailer with bathroom paper goods, soap, broom, mop and doormats.
- H. Trailer shall remain property of CONTRACTOR. CONTRACTOR shall remove such property upon Substantial Completion of Work or as otherwise determined in writing by OAR.

1.07 FURNISHINGS

- A. CONTRACTOR shall provide new furnishings in the following quantities, shall set in rooms and shall position as directed by OAR upon delivery:
 - 1. 4 desks, 30 by 66 by 30 inches: Haworth Adaptables WURA-3066-LJSC H-AE Graphite worksurface, Haworth Reside Adjustable Hoop Leg ZKH2-3000-PNFD TR-J Graphite (2 per desk), Haworth X Series Pedestal JPMH-24-SJ B/B/F TR-J Graphite (2 per desk), lifetime warranty, or equal, shall be provided new and shall remain as CONTRACTOR's property.

2. 1 metal bookcases, three shelf, 41 by 34 by 12 inches; HON Brigade or equal (Similar to Staples Cat.# 793638; Item: 1598509/ Model: HS42ABCL).
3. 4 resin folding tables, 29 by 30 by 72 National Public Seating BT3072, 10 year warranty, or equal, shall be provided new and shall remain as CONTRACTOR's property.
4. Provide and install 2 large white board in one conference room, 48 by 72 inches, Quartet melamine dry-erase board or equal. (Similar to Staples Cat. # 789834/Model: S538) and shall remain as CONTRACTOR's property.
5. Provide and install 1 large tack board in the other conference room, 48 by 72 inches, Quartet cork bulletin board or equal. (Similar to Staples Cat. # 789842/Model: QRT2308) and shall remain as CONTRACTOR's property.
6. Provide and install one (1) refrigerator, 61 3/4"H by 28" W by 32 5/8D, 15.6 Cubic Feet, GE Energy Star, Model #GTE16RTNRWW and shall remain as CONTRACTOR's property.
7. Provide and install one (1) microwave, 19.44" D by 23.88" by 14" H, 2.2 cu ft., Panasonic, Model No. NN-SN936B and shall remain as CONTRACTOR's property.
8. Miscellaneous Office Equipment: Provide new and not refurbished the following:

Project Documentation Camera

(1) Sony Cyber-shot RX100 Vii compact camera with two additional camera batteries and compatible Sony battery charger.

(2) Camera Storage Case – JINHEI Hard EVA Carrying Storage Case (Amazon)

(3) SD Card – Sandisk – 128 GB Extreme Pro SDXC UHS-II Memory Card UHD
9. One (1) hard copy and One (1) CD of each of the most current version of the following publications shall be provided. Provide publications updates annually within 14 days of their commercial availability and shall remain the DISTRICT's property.

- a. RS Means Building and Renovation Schools
- b. RS Means Facilities Construction Cost Data

B. Unless otherwise noted in this Section, all furniture shall remain property of CONTRACTOR. CONTRACTOR shall remove such property upon Substantial Completion of Work or as otherwise determined in writing by OAR.

1.08 TELEPHONE & DATA AND TRANSMISSION LINES

A. (NOT USED)

B. Printer/Copier/Scanner: Provide, install, configure and maintain for network connectivity one HP LaserJet MFP M880z+ (or latest HP equivalent model at time of bid) with the following features and accessories:

1. Supplies: CONTRACTOR shall provide the following:

- a. All toner supplies and consumables, including enough supplies to maintain 4 spares of each color toner.
- b. All staples and other printer-related consumables, including enough supplies to maintain one spare staple cartridge.

C. Electronic/office equipment shall be new at the commencement of the project.

1.09 TEMPORARY STORAGE UNITS

A. CONTRACTOR shall provide secure and waterproof storage units for the temporary storage of furniture, equipment and other items requiring protection.

B. Walls, roof and doors shall be a minimum of 16-gauge steel with floors of 1 inch tongue and groove hardwood or ¾ inch minimum exterior type plywood. The undercarriage shall be designed to accommodate forklift blades 42-inch to 60-inch long. There shall be doublewide swing out lockable doors at one end equipped with waterproof gaskets.

C. CONTRACTOR shall be responsible for delivery charges and will install the storage unit in an appropriate area.

D. CONTRACTOR shall remove the storage unit from the Project site when the storage unit is no longer required for the Work or upon Substantial Completion of the Work.

- E. CONTRACTOR shall at their expense and without limitation remove and/ or relocate storage units as rapidly as required in order to provide for progress of the Work.

1.10 TEMPORARY SANITARY FACILITIES

- A. CONTRACTOR shall provide portable chemical toilet facilities. Quantity of portable chemical toilet facilities shall be based on total number of workers and shall be in accordance with CAL/OSHA standards.
- B. Portable chemical toilet facilities shall be maintained with adequate supplies and in a clean and sanitary condition and shall be removed from the Project site upon Substantial Completion of the Work. CONTRACTOR shall keep both OWNER chemical toilet facilities and OWNER trailer restroom clean and operational at all times.
- C. CONTRACTOR employees shall not use school toilet facilities.
- D. At CONTRACTOR'S expense and without limitation remove and/or relocate portable chemical toilet facilities as rapidly as required in order to provide for progress of the Work.
- E. CONTRACTOR will contain their breaks and lunch periods to the areas designated by OAR or any public area outside the Project site. CONTRACTOR shall provide a suitable container within the break/lunch area for the placement of trash. Areas used for break/lunch must be maintained clean and orderly. Once finish flooring has been installed in a particular area, no food or beverages will be permitted in that area.

1.11 TEMPORARY SECURITY FENCE / BARRICADE

- A. CONTRACTOR shall install temporary Project site security barricade(s) indicated on Drawings or as required for safety and as specified herein. New or used material may be furnished. Security of Project site and contents is a continuous obligation of CONTRACTOR.
- B. Unless otherwise indicated or specified, security fence shall be constructed of 8-foot high chain link fencing with an 8-foot high windscreen. Space posts not to exceed ten feet on centers. Posts shall be of following nominal pipe dimensions: terminal, corner, and gatepost 2 ½-inch, line posts 2-inch. Chain link fence shall be not less than #13 gauge, 2-inch mesh, and in one width. Posts, fence and accessories shall be galvanized and as follows:
 - 1. Shall be set in the earth a depth of 24-inch with soil firmly compacted around post, unless required otherwise in writing by OAR.

2. Fence fabric shall be attached to posts with #14 gauge tie wire at 16 inches on center. A #6 gauge steel tension wire with turnbuckles shall be installed at top and bottom of barricade fencing. Wire tie fabric to tension wires at 18" centers.
3. Windscreen shall be attached to fence fabric and steel tension wires at 18-inch centers with a minimum of #14 gauge tie wire. Windscreen shall be maintained and all rips, tears, missing sections shall be corrected upon notification by OAR.
4. Chain link fencing shall be free from barbs, icicles or other projections resulting from galvanizing process. Fence having such defects will be replaced even if it has been installed.
5. Gates shall be fabricated of steel pipe with welded corners and bracing as required. Fence and fabric to be attached to frame at 12-inch centers. Provide all gate hardware of a strength and quality to perform satisfactorily until barricade is removed upon Substantial Completion of the Work. Each gate shall have a chain and padlock. Provide two gate keys to OAR. At Substantial Completion of the Work, remove barricade from Project site, backfill and compact fence footing holes. Existing surface paving that is cut into or removed shall be patched and sealed to match surrounding areas.
6. At CONTRACTOR'S expense and without limitation remove or relocate fencing, fabric and barricades or other security and protection facilities as rapidly as required in order to provide for progress of the Work.

1.12 OTHER TEMPORARY ENCLOSURES AND BARRICADES

- A. Provide lockable, temporary weather-tight enclosures at openings in exterior walls to create acceptable working conditions, to allow for temporary heating and for security.
- B. Provide protective barriers around trees, plants and other improvements designated to remain.
- C. Temporary partitions shall be installed at all openings where additions connect to existing buildings, and where to protect areas, spaces, property, personnel, students and faculty and to separate and control dust, debris, noise, access, sight, fire areas, safety and security. Temporary partitions shall be as designated on the Drawings or as specified by ARCHITECT. At CONTRACTOR'S expense and without limitation remove and/or relocate enclosures, barriers and temporary partitions as rapidly as required in order to provide for progress of the Work.
- D. Since the Work of this Project may be immediately adjacent to existing occupied structures and vehicular and pedestrian right of ways, CONTRACTOR shall, in

his sole judgment and in accordance with applicable safety standards, provide temporary facilities, additional barricades, protection and care to protect existing structures, occupants, property, pedestrians and vehicular traffic. CONTRACTOR is responsible for any damage, which may occur to the property and occupants of the property of OWNER or adjacent private or public properties which in any way results from the acts or neglect of CONTRACTOR.

- E. CONTRACTOR shall be responsible for cleaning up all areas adjacent to the construction site which have been affected by the construction; and for restoring them to at least their original condition- including landscaping; planting of trees, sod, and shrubs damaged by construction; and raking and disposal of debris such as roofing shingles, paper, nails, glass sheet metal, bricks, and waste concrete. Construction debris shall be removed and properly disposed of. Culverts and drainage ditches with sediment from the construction area shall be cleared routinely to maintain proper drainage and re-cleaned prior to completion of the contract.
- F. CONTRACTOR shall ensure sediment does not block storm drains. CONTRACTOR shall be responsible for cleaning storm drains blocked due to erosion or sediment from the work area.

1.13 TEMPORARY STORAGE YARDS

- A. CONTRACTOR shall fence and maintain storage yards in an orderly manner.
- B. Provide storage units for materials that cannot be stored outside.
- C. At CONTRACTOR'S expense and without limitation remove and/or relocate storage yards and units as rapidly as required in order to provide for progress of the Work.

1.14 TEMPORARY DE-WATERING FACILITIES AND DRAINAGE

- A. For temporary drainage and de-watering facilities and operations not directly associated with construction activities included under individual sections, comply with de-watering requirements of applicable Division 01 sections. CONTRACTOR shall maintain the Work, Project site and related areas free of water.
- B. For temporary drainage and de-watering facilities and operations directly associated with new buildings, additions or other construction activities, comply with Divisions 01 and 33 Sections. CONTRACTOR shall be responsible for, but not limited to, de-watering of excavations, trenches and below grade areas of buildings, structures, the Project site and related areas.

1.15 TEMPORARY PROTECTION FACILITIES INSTALLATION

- A. CONTRACTOR shall not change over from using temporary facilities and controls to permanent facilities until Substantial Completion, except as permitted by OAR.
- B. Until permanent fire protection needs are supplied and approved by authorities having jurisdiction, CONTRACTOR shall provide, install and maintain temporary fire protection facilities of the types needed in order to adequately protect against fire loss. CONTRACTOR shall adequately supervise welding operations, combustion type temporary heating and similar sources of fire ignition.
- C. CONTRACTOR shall provide, install and maintain substantial temporary enclosures of partially completed areas of construction. Provide locking entrances to prevent unauthorized entrance, vandalism, theft and similar violations of security. Where materials, tools and equipment are stored within the Work area, CONTRACTOR shall provide secure lock up to protect against vandalism, theft and similar violations of security. OWNER accepts no financial responsibility for loss, damage, vandalism or theft.
- D. CONTRACTOR operations shall not block, hinder, impede or otherwise inhibit the use of required exits and/or emergency exits to the public way, except as approved by OAR. CONTRACTOR shall maintain unobstructed access to fire extinguishers, fire hydrants, temporary fire protection facilities, stairways and other access routes for firefighting equipment and/or personnel.
- E. With approval of OAR and at the earliest feasible date in each area of the Work, complete installation of the permanent fire protection facilities including connected services and place into operation and use. Instruct OWNER personnel in use of permanent fire protection facilities.
- F. In the event of an emergency drill or an actual emergency, designated by the sounding of the fire alarm and/or other sounding device, all construction activities must cease. CONTRACTOR shall evacuate the Work area and remain outside the Work area until permitted to return. No Work shall be conducted during the evacuation of a building or during an emergency.

1.16 TEMPORARY SECURITY AND SAFETY MEASURES

- A. During performance of the Work in existing facilities and/or on a Project Site occupied by students, CONTRACTOR shall provide, install and maintain substantial temporary barriers and/or partitions separating all Work areas from areas occupied by students, faculty and/or administrative staff.
- B. During performance of the Work in existing facilities or on a Project site occupied by students and where temporary barriers or partitions are not physically feasible, CONTRACTOR shall provide an employee meeting the requirements of Education Code Section 45125.2.(2) to continually supervise and monitor all employees of CONTRACTOR and Subcontractor. For the purposes of this

Section, CONTRACTOR employee shall be someone whom the Department of Justice has ascertained has not been convicted of a violent or serious felony as listed in Penal Code Section 667.5(c) and/or Penal Code Section 1192.7(c). To comply with this Section, CONTRACTOR shall have his employee submit his or her fingerprints to the Department of Justice pursuant to Education Code Section 45125.1(a).

- C. Penal Code Sections 290 and 290.4 commonly known as “Megan’s Law”, require, among other things, individuals convicted of sexually oriented crimes, to register with the chief of police where the convicted individual resides or with a county sheriff or other law enforcement officials. CONTRACTOR shall check its own employees and require each Subcontractor to check its employees and report to CONTRACTOR if any such employees are registered sex offenders. CONTRACTOR shall check monthly during the life of the Contract to ascertain this information and report same to OAR. Before starting the Work, and monthly thereafter during the life of Contract, CONTRACTOR shall notify OWNER in writing if any of its employees and/or if any Subcontractor’s employees is a registered sex offender. If so, CONTRACTOR shall proceed in accordance with paragraph B above.
- D. CONTRACTOR shall employ and maintain sufficient security and safety measures to effectively prevent vandalism, vagrancy, theft, arson, and all other such negative impacts to the Work. Any impacts to the progress of the Work of CONTRACTOR, OWNER, or OWNER’S forces, due to loss from inadequate security, will be the responsibility of CONTRACTOR.
- E. Until Substantial Completion of the Work, CONTRACTOR shall employ appropriate means to remove all graffiti from buildings, equipment, fences and all other temporary and/or permanent improvements on the Project site within twenty-four (24) hours from the date of report or forty-eight (48) hours of each occurrence.

1.17 TEMPORARY ACCESS ROADS AND STAGING AREAS

- A. Due to the limited amount of on and off Project site space for the parking of staff and school visitor’s vehicles there will be no parking of CONTRACTOR vehicles in areas designated for school use only. CONTRACTOR shall provide legal access to and maintain CONTRACTOR designated areas for the legal parking, loading, off-loading and delivery of all vehicles associated with the Work. CONTRACTOR shall be solely responsible for providing and maintaining these requirements whether on or off the Project site. CONTRACTOR shall provide and maintain ample on-site parking spaces designated for the exclusive use of OWNER. CONTRACTOR shall erect signs as required by OWNER each of these spaces and prevent all unauthorized vehicles from parking in the OWNER-reserved spaces.

- B. Temporary access roads are to be installed and maintained by CONTRACTOR to all areas of the Project site.
- C. CONTRACTOR will be permitted to utilize existing facility campus roads as designated by OAR. CONTRACTOR shall only utilize those entrances and exits as designated by OAR and CONTRACTOR shall observe all traffic regulations of OWNER.
- D. CONTRACTOR shall maintain roads and walkways in a clean condition including removal of debris and/or other deleterious material on a daily basis.

1.18 DIRECTIONAL SIGNAGE AND ADVERTISEMENT POSTING

- A. CONTRACTOR shall provide and install signage to provide directional, identification, and contact information to construction personnel and visitors as follows and as reviewed by OAR.
 - 1. For construction traffic control/flow at entrances/exits, and as designated by OAR.
 - 2. To direct visitors.
 - 3. For construction parking.
 - 4. To direct deliveries.
 - 5. For Warning Signs as required.
 - 6. In accordance with CAL/OSHA standards as necessary.
 - 7. For trailer identification and Project site address.
 - 8. For "No Smoking" safe work site at designated locations.
 - 9. Emergency contact information and phone number of CONTRACTOR.
 - 10. Emergency contact information and phone number of local police, fire, and emergency personnel.
 - 11. For Labor Compliance Program (LCP) as required under the General Conditions (Prevailing wage rates and Notice of LCP)
 - 12. Employee benefits payments paid to trust funds are required under the General Conditions.
- B. OWNER has established a program authorizing vendors to post advertisements and billboards along the perimeter of project site. CONTRACTOR shall provide

access and shall allow advertising signage to be placed on top of temporary, perimeter, security barricade and/or fences.

1.19 TRENCHES

- A. Open trenches for installation of utility lines (water, gas, electrical and similar utilities) and open pits outside barricaded working areas shall be barricaded at all times in a legal manner determined by CONTRACTOR. Trenches shall be backfilled and patch-paved within twenty-four (24) hours after approval of installation by authorities having jurisdiction or shall have "trench plates" installed. Required access to buildings shall be provided and maintained. CONTRACTOR shall comply with all applicable statutes, codes and regulations regarding trenching and trenching operations. Open trenches deeper than 3'-6", and not located within a public street access, shall be enclosed within an 8'-0" high chain-link fence.

1.20 DUST CONTROL

- A. CONTRACTOR is responsible for dust control on and off the Project site. When Work operations produce dust the Project site and/or streets shall be sprinkled with water to minimize the generation of dust. CONTRACTOR shall clean all soils and debris from construction vehicles and cover both earth and debris loads prior to leaving the Project site. CONTRACTOR shall, on a daily basis, clean all streets and/or public improvements within the right of way of any and all debris, dirt, mud and/or other materials attributable to operations of CONTRACTOR.

1.21 WASH OUT

- A. CONTRACTOR shall provide and maintain a minimum of four (4) wash out boxes of sufficient size and strength to provide for concrete mixer wash out. CONTRACTOR shall locate and relocate both the wash out boxes and wash out areas in order to accommodate the progression of the Work. The wash out area shall be located as to minimize the amount of potential run off onto adjacent private and/or public property. CONTRACTOR shall legally dispose of the contents of the wash out boxes and area on an as needed basis or as required by OAR.

1.22 WASTE DISPOSAL

- A. CONTRACTOR shall provide and maintain trash bins on the Project site. Trash bins shall be serviced on an as needed basis and CONTRACTOR is responsible for the transportation of and the legal disposal of all contents.

1.23 ADVERSE WEATHER CONDITIONS

- A. Should warnings of adverse weather conditions such as heavy rain and/or high winds be forecasted, CONTRACTOR shall provide every practical precaution to prevent damage to the Work, Project site and adjacent property. CONTRACTOR precautions shall include, but not be limited to, enclosing all openings, removing and/or securing loose materials, tools, equipment and scaffolding.
- B. CONTRACTOR shall provide and maintain drainage away from buildings and structures.
- C. CONTRACTOR shall implement all required storm water mitigation measures as required under related Division 01 Sections.

1.24 DAILY AND MONTHLY REPORTS

- A. CONTRACTOR shall provide and maintain in the Project site office of CONTRACTOR, a daily sign in sheet for use by all employees of CONTRACTOR and all Subcontractors at whatever tier. At the beginning of each workday, the foreman, project manager, superintendent of CONTRACTOR and/or Subcontractors shall visit the site office of CONTRACTOR and shall enter onto the daily sign in sheet: all employee names; trade classification; and represented company. The completed sign in sheet shall serve as the basis of and shall be submitted with the daily construction report as set forth in Paragraph B below.
- B. By the end of each workday, CONTRACTOR shall submit to OAR and IOR a daily construction report denoting the daily manpower counts and a brief description/location of the workday activities. Manpower shall be broken down by trade classification such as foreman, journeyman or apprentice. The report shall also note the date, day of the week, weather conditions, deliveries, equipment on the Project site whether active and/or idle, visitors, inspections, accidents and unusual events, meetings, stoppages, losses, delays, shortages, strikes, orders and requests of governing agencies, Construction Directive and/or Change Orders received and implemented, services disconnected and/or connected, equipment start up or tests and partial use and/or occupancies. CONTRACTOR shall also include on the daily construction report the above information for all Subcontractors at whatever tier.
- C. CONTRACTOR shall submit on a monthly basis the forms found in Sections 01 3229 and 01 7416 certifying CEQA Mitigations and Storm Water Pollution Prevention (SWPP) compliances.

1.25 FIELD OFFICE SUPPLIES

- A. CONTRACTOR shall provide the initial supply of field office supplies to OAR in the quantities listed as set forth below in Table A. If specified in Section 01 2100 – Allowances, CONTRACTOR shall provide additional supplies as required by

OAR. CONTRACTOR shall not deduct the costs of the Initial Field Office Supplies (as shown in Table A) from the Allowance for the monthly replenishment of OWNER field office supplies listed in Section 01 2100 – Allowances. CONTRACTOR shall deliver all of the initial field office supplies to OWNER Field Offices within fourteen days from the date established in the Notice to Proceed.

- B. CONTRACTOR may utilize different suppliers as the specified information is only to establish the required quantities and minimum levels of quality.
- C. Replenishment of Field Office Supplies: If an Allowance is identified in Section 01 2100 – Allowances for the periodic replenishment of OWNER field office supplies. OWNER shall submit requests for replenishment of field office supplies to CONTRACTOR from those listed in Table ‘A’ below. CONTRACTOR shall provide a monthly accounting of items being requested, cumulative cost of replenishment of Field Office supplies previously ordered, and balance of allowance remaining. Upon Substantial Completion of the Work, CONTRACTOR shall file a Change Order Proposal crediting OWNER for any remaining balance or unspent portion of the Allowance. This Allowance specifically excludes the initial supplies listed in Table ‘A’ below and is to be used exclusively for the monthly replenishment of OWNER field office supplies. Supplies are to be delivered to OWNER’S trailer within twenty-four hours of OWNER’S request.
- D. Postage and Delivery Costs: CONTRACTOR shall provide postage and delivery services for OWNER generated materials in quantities and/or frequencies as requested by OWNER. The cost for these services shall be deducted from the Allowance identified in Section 01 2100 – Allowances for the periodic replenishment of OWNER field office supplies. This allowance is for the OWNER’S use only. Postage and delivery costs for CONTRACTOR generated materials are the responsibility of the CONTRACTOR and shall not be charged to this allowance, regardless of whether the postage and/or delivery of CONTRACTOR generated materials resulted from a request and/or direction from OWNER.
- E. Other expendable field office support items specified elsewhere, including, but not limited to, furnishing toner cartridges, equipment maintenance, and bottled water, are to be supplied and paid for by CONTRACTOR. These costs are not to be deducted from the Allowance for the periodic replenishment of OWNER field office supplies identified in Section 01 2100.

Table A				
ITEM	DESCRIPTION	UNIT	QUANTITY	SUPPLIER/ITEM NUMBER
Three Ring Binders – 3-inch	N/A	Each	0	Staples / 823526-54
Three Ring Binders – 2-inch	N/A	Each	0	Staples / 816199-54
Three Hole Punch	N/A	Each	0	Staples / 893844
Two Hole Punch	N/A	Each	0	Staples / 506261-54

File Organizer	N/A	Each	0	Staples / 120162-54
Flash Drive	2 GB	2	5	
Wastebasket	N/A	Each	3	Staples / 125039-54
Surge Suppressors	N/A	Each	4	Staples / IM1RA1696
Flashlight	N/A	Each	3	Staples / 222397
Batteries	N/A	4/Lot	3	Staples / 318956-54
Clipboard	N/A	3/Lot	2	Staples / 450422-54
8-inch Cast Iron Shears	N/A	Each	2	Staples / 421040-54
First Aid Kit	N/A	Each	1	Staples / 503979-54
Journal	N/A	Each	5	Staples / 217695-54
Clipboards	Black	Each	5	Brand Ruby Paulina (Amazon) Color: Black - 11x17 Clipboard with 8-inch metal hinge clip. 19.5 inches in length. Extra large, thick acrylic clip board for drawing, engineering, drafting, art, and more.
Pens (blue, green and red)	N/A	12/Lot	3	Staples / 441884-64
Pencils	N/A	48/Lot	2	Staples / 711382-54
Pencil Sharpener	1900	1	1	Staples / 330250-54
Mouse Pad	N/A	Each	3	Staples / 382955-64
Date Received Stamp	N/A	Each	1	Staples / 920274-54
Colored Pencils	N/A	12/Lot	0	Staples / 317297-54
Markers	N/A	12/Lot	1	Staples / 932675
Wall Calendar	PM233-28	Each	1	Staples / 527861-54
Legal Pad	N/A	12/Lot	1	Staples / 163865-64
Post Its	N/A	12/Lot	6	Staples / 130005-64
File Folders – 8-1/2 by 11	N/A	50/Lot	1	Staples / 831099-54
File Folders – 8-1/2 by 14	N/A	50/Lot	1	Staples / 831057-54
Tape / Dispenser	N/A	Each	2	Staples / 211540-54
Highlighters	N/A	12/Lot	2	Staples / 167031
Rubber Bands	N/A	Each	1	Staples / 808634
Push Pins	N/A	Each	1	Staples / 480118-54
Dry Erase Board	S537	Each	2	Staples / 518928-54
Binder Clip – Medium	N/A	24/Lot	3	Staples / 831602-54
Binder Clip - Large	N/A	12/Lot	3	Staples / 831610-54
Stapler	818	Each	4	Staples / 504308
3 Pocket Wall File	N/A	Each	2	Staples / 730523-54
Heavy Duty Stapler	415	Each	1	Staples / 386312-54
Heavy Duty Staples	SW1-35312	Each	1	Staples / 504191-54
Hanging File Folder	8-1/2 x 11	25/Lot	0	Staples / 116806-54
Hanging File Folder	8-1/2x14	25/Lot	0	Staples / 163352-54
File Folder Labels	5266	750/Lot	0	Staples / 287292-54
Paper Clips	N/A	Each	4	Staples / 480108-54
Paper Clips	N/A	Each	4	Staples / 480109-54
Poster Kit - State	CA	Each	1	Staples / 1183148
Poster Kit - Federal	US	Each	1	Staples / 935983-54
Broom	N/A	Each	1	Staples / 256600
Fire Extinguisher	First Alert	Each	1	Staples / 238774-54
Copy Paper	8-1/2 x 11	5000/Case	5	Staples / 122374-69
Copy Paper	8-1/2 x 14	500/Ream	5	Staples / 122598-69
Copy Paper	11 x 17	500/Ream	1	Staples / 238105-69

Hardhats* Contractor shall have three LAUSD logos printed on the hardhat. Two MOX logos on right and left side and one District logo at the front of the hardhat Artwork to be provided by District for contractor to digitize and create an file acceptable to the printer company.	Gray	Each	10	Fibre-Metal Gray Full Brim Hard Hat with Ratchet Suspension/ MFG# E1RW09A000
Safety Glasses	Clear and/or Tinted	Each	10	Crews Storm Series
Digital Camera	20.1 MP	Each	1	Sony Cyber-shot RX100Vii w/ battery
Camera Storage Case		Each	2	JINHEI Hard EV A Carrying Case (Amazon)
Camera Flash Memory with reader for computer	128 GB	Each	3	Sandisk – 128 GB Extreme Pro SDXC UHS-II Memory Card UHD
Camera Batteries and Rechargeable Batteries with charger	(2) additional camera batteries and compatible Sony battery charger	Each	3	
Safety Vests** ** (Contractor shall provide the safety vests with LAUSD logos printed on them (front and back). Logos artwork PDF to be provided by District)	FIRST LADY Safety Vest for Women, High Visibility Reflective Strips, Meets ANSI & OSH – Size Medium	Each	3	KwikSafety – Charlotte, NC – (Amazon)
Safety Vests** ** (Contractor shall provide the safety vests with LAUSD logos printed on them (front and back). Logos artwork PDF to be provided by District)	FIRST LADY Safety Vest for Women, High Visibility Reflective Strips, Meets ANSI & OSH – Size Large	Each	3	KwikSafety – Charlotte, NC – (Amazon)
Safety Vests** (Contractor shall provide the safety vests with LAUSD logos printed on them (front and back). Logos artwork PDF to be provided by District)	Unisex High Visibility Reflective Premium Black Series Black Bottom – Size Medium	Each	4	Kishigo
Safety Vests** ** (Contractor shall provide the safety vests with LAUSD logos printed on them (front and back). Logos artwork PDF to be provided by District)	Unisex High Visibility Reflective Premium Black Series Black Bottom – Size Large	Each	5	Kishigo
Safety Vests** ** (Contractor shall provide the safety vests with LAUSD logos printed on them (front and back). Logos artwork PDF to be provided by District)	Unisex High Visibility Reflective Premium Black Series Black Bottom – Size X Large	Each	6	Kishigo
Safety Vests** ** (Contractor	Unisex High Visibility	Each	4	Kishigo

shall provide the safety vests with LAUSD logos printed on them (front and back). Logos artwork PDF to be provided by District)	Reflective Premium Black Series Black Bottom – Size XX Large			
---	--	--	--	--

*Contractor shall have three LAUSD logos printed on the hardhat. Artwork to be provided by District.

**Contractor shall provide the safety vests with LAUSD logos printed on them (front and back). Logos artwork PDF to be provided by District.

PART 2 – PRODUCTS – Not Used

PART 3 – EXUTION – Not Used

END OF SECTION

APPENDIX A





Your School Bond Dollars At Work

Thank-you for Championing School Safety & Inclusion!

\$140M Investment

Construction Start 2020

Alberto M. Carvalho

Superintendent

Karla Griego

Board Member District 5

Logo & Architect

Logo & Contractor

Follow us on  @lausd_facilities

Elizabeth Learning Center

Comprehensive Modernization Project

END OF APPENDIX A